Code: CE4T2

II B. Tech - II Semester – Regular Examinations - JUNE 2015

GEOTECHNICAL ENGINEERING-I (CIVIL ENGINEERING)

Duration: 3 hours

Marks: 5x14=70

Answer any FIVE questions. All questions carry equal marks

- a) Derive a relationship between voids ratio, water content, specific gravity of particles and degree of saturation.
 7 M
 - b) In a compaction test on a soil the mass of wet soil when compacted in the mould was 1.9kg. The water content of the soil was 16.5%. If the volume of the mould was 0.94 litres, Determine dry density, void ratio, degree of saturation and percentage air voids. Take G=2.68. 7 M
- 2. a) Explain the test procedure to determine shrinkage limit of a soil.

 7 M
 - b) The consistency limits of a soil are LL = 52%, PL = 32% and SL= 17%. If the soil shrinks from a volume of 10cm³ at LL to 6.01cm³ at shrinkage limit, calculate the specific gravity of solids.
- 3. a) In a falling head permeameter, if the time intervals for drop in levels from H_1 to H_2 and H_2 to H_3 are equal, prove that $H_2 = \sqrt{(H_1 * H_3)}$.

- b) What are the different parameters of the soils that influence the permeability of soils?

 7 M
- 4. a) What are the characteristics of flow nets? Explain in detail the methods of constructing the same.

 7 M
 - b) What is quick sand condition? List out the conditions that are favorable for quick sand condition.

 7 M
- 5. a) Derive an expression for vertical stress at a point due to vertical load. Use Boussinesq's theory.

 7 M
 - b) Two columns A and B are 5m apart. Column A transfers a load of 400kN and that of B is 600kN. Determine the vertical stress beneath these columns at a depth 4m below.

 7 M
- 6. a) What are the factors that affect the compaction properties of soils? Discuss in brief.

 7 M
 - b) The observations of a compaction test are as follows:

| Water Content (%) | 7.7 | 11.5 | 14.6 | 17.5 | 19.7 | 21.2 |
|-------------------|-----|------|------|------|------|------|
| Mass of wet soil | 1.7 | 1.89 | 2.03 | 1.99 | 1.96 | 1.92 |
| (kg) | | | | | | |

Volume of the mould is 950cm³. Take G=2.65; Plot the water content- dry density curve and determine the optimum water content and Maximum dry density. 7 M

- 7. a) Explain Terzaghi's theory of consolidation. Discuss the assumption and their validity.

 7. a) Explain Terzaghi's theory of consolidation. Discuss the assumption and their validity.
 - b) A 3m thick clay layer beneath a structure is overlain by a permeable stratum and is underlain by an impervious stratum. The coefficient of consolidation of the clay was found to be $0.028 \text{cm}^2/\text{minutes}$. The final expected settlement of the layer is 80mm. Determine the time taken for 75% of full consolidation and the time required for 2.5cm settlement.
- 8. a) What are the merits of tri axial shear test over box shear test? Explain the different conditions for which soils under tri axial tests can be conducted.

 7 M
 - b) The following are the results of box shear test on a soil.

| Normal Stress(kPa) | 25 | 75 | 150 | 250 |
|------------------------------|----|----|-----|-----|
| Shear stress at failure(kPa) | 55 | 75 | 100 | 140 |

Determine cohesion and angle of internal friction of the soil. Also determine the deviator stress required for the failure of the same soil specimen under triaxial test with a cell pressure of 100 kPa.

7 M